



AI-generated conceptual image; final configuration is project-specific.

AUTOMATIC LIQUID DOSING & FILLING SYSTEM

Automatic Load Cell Liquid Filling Machine

For approved bottles, jars, cans or pails with compatible liquids, with conveyor or platform positioning on individual weighing stations.

Suitable for: Approved bottles, jars, cans or pails with compatible liquids

Machinery supply within India only. Technical review, delivery and support are coordinated from Ahmedabad.

Operating Principle and Selection Basis

The empty container is tared on a load cell, filled at coarse rate and then fine rate, and stopped when the target net weight is reached.

Control System: Recipe, tare, coarse/fine flow and weight-tolerance control

Optional Scope: Number of stations, weighing range, reject system and data reporting are configurable.

Project basis: Final specifications are governed by the approved quotation, machine datasheet, GA drawing and project URS. Published references and configuration/order qualifiers are retained. Illustrated equipment is not a guarantee of the supplied configuration.

Published Technical Specifications

Source: the product page included in this release. Published references are selection aids; the approved quotation and machine datasheet govern the supplied configuration.

Machine, Process and Integration Data

PARAMETER	PUBLISHED / PROJECT DATA
Suitable For	Approved bottles, jars, cans or pails with compatible liquids
Working Principle	The empty container is tared on a load cell, filled at coarse rate and then fine rate, and stopped when the target net weight is reached.
Infeed / Handling	Conveyor or platform positioning on individual weighing stations
Outfeed / Transfer	Accepted containers discharge; reject handling can be integrated
Machine Construction	GMP-oriented stainless-steel construction as defined in the approved scope
Contact Materials	Product-contact materials, seals, tubing, valves and surface finish are matched to the product and cleaning method in the approved scope.
Control System	Recipe, tare, coarse/fine flow and weight-tolerance control
Changeover	Settings, guides and format parts matched to approved samples or drawings
Optional Scope	Number of stations, weighing range, reject system and data reporting are configurable.
Line Integration	Standalone supply or integration with approved upstream and downstream machines

Core Technical and Commercial Data

PARAMETER	PUBLISHED / PROJECT DATA
Model / Series	Configuration-specific. The model code is assigned in the approved quotation after the product, pack, process and automation scope are fixed.
Output / Throughput	Configuration-specific. The rated output in containers per minute depends on fill volume, viscosity, temperature, foam, container, dosing technology and number of filling heads.
Accuracy / Acceptance Criterion	Configuration-specific. Filling tolerance and the FAT sampling method are guaranteed only for the approved product, dose, container and operating conditions.
Electrical Power	Configuration-specific. Voltage, phase, frequency and maximum connected load are stated in the approved electrical load list.
Utilities	Configuration-specific. Electrical supply, compressed air, product feed or temperature control, gas or vacuum, and cleaning or CIP interfaces are listed as applicable.
Overall Dimensions (L × W × H)	Overall dimensions are model- and configuration-specific. Final L × W × H is confirmed in the customer-approved GA drawing based on capacity, output, process requirements and site layout before order execution.
Net / Shipping Weight	Configuration-specific. Net and packed shipping weights are stated in the approved datasheet or packing list.
Capacity / Format Range	Configuration-specific. Fill-volume range, approved container range and any product holding capacity are stated in the machine datasheet.
Warranty	Order-specific. Duration, commencement date, covered parts, exclusions and claim terms are stated in the approved quotation or order.
Installation / Commissioning Scope	Order-specific. The quotation states whether installation, commissioning, SAT and operator training are included, together with unloading, positioning, utilities, civil work, trial materials, travel and site responsibilities.